No.	Items of work	Unit	Rate	Quantity	Cost
	Constructing 2 masonry sluices—Details for one sluice.		Rs. a. p.		Rs.
1	Earthwork for cutting and opening the bund for sluice work.	C.yd.		193	
2	Stone jelly concrete in surki mortar	C.ft.		449	
3	Burnt brick in surki mortar	,,		753	
4	Burnt stone slabs dressed and fixed	S.ft.		232	
5	Plastering with surki mortar	Sqr.		8·00	
6	Earthwork filling the opening with watering and tamping, etc.	C.yd.		193	
7	Cutting holes in orifices and guide and gibbet slabs	each		4	
8	Providing wooden plug with iron rod and locking arrangements.		Lump sum		
	Constructing right waste weir 200 feet long.				
1	Earthwork excavation, foundation and making use the earth for training bank with watering, etc., complete.	C.yd.		463	
2	Jelly concrete in surki mortar	C.ft.		684	
3	Burnt brick in surki mortar	,,		1,143	
4	Plastering in surki mortar	Sqr.		17·35	
5	Burnt stone slabs 6 inches thick dressed and fixed	S.ft.		586	
6	Rough stone work with jelly packing ...	C.yd.		132	
7	Earthwork excavation approach and draft clearing	,,		7,708	

N. G. KRISHNA IYENGAR,
Executive Engineer.

SANITARY AND TOWN PLANNING DIVISION.

Dated 15th August 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Sanitary and Town Planning Division, up to 12 noon on 6th September 1929, for the supply of sanitary fittings and galvanized iron pipes and fittings required for "Providing Sanitary Fittings to Mr. Munivenkatappa's Wards at the Tuberculosis Sanatorium Hospital, Mysore, and for the New Operation Theatre of Vani Vilas Hospital, Mysore". An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th October 1929.

2. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed,

3. Each tender must be accompanied by a deposit of Rs. 50 in Cash or Government Promissory Notes, as earnest money and be superscribed "Tender for the supply of sanitary Fittings and Galvanized Iron Pipes", in default of which tenders will be rejected.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. Within eight days of acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

6. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No. enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

8. In all matters of disputes not specially provided for and in all matters of disputes about rates, quantities, measurements and quality of work and in all disputes of any kind, the decision of the Chief Engineer, will be final and legally binding.

List of materials for providing Sanitary fittings to the New Operation Theatre of Vani Vilas Hospital, Mysore.

Sl. No.	Name of article	Unit	Quantity
	I. Sanitary Fittings.		
1	H. 4000 Shanks' Lavatory for Surgeons in whiteglazed earthenware, H. 4060 elbow action mixing fitting in polished gunmetal with ½″ inlets and rose outlet 1½″ vulcanite standing waste and overflow, polished gun metal hook for hanging the waste H. 4054 white porcelain enamelled cast iron brackets for screwing to wall.	No.	2
2	H. 4876 Shank's plain-edge sink with high back in 'Victorian' fireclay, white glazed inside and outside with tap holes through back and with H. 4521 plug and chain waste H. 4055 painted cost iron brackets H. 4889 hot and cold taps size of sink 30″ x 18″ x 10″.	,,	2
3	H. 4635 Shank's plate glass shelf with nickel plated brass brackets and guard rail 30″ x 6″ x 3/8″.	,,	2
4	H. 631 Shank's adjustable towel rails with 3 arms length of arm 15″.	,,	2
	II. Stoneware Materials, etc., for drains.		
1	6″ x 4″ stoneware gully trap with cast iron grating ...	,,	2
2	4″ stoneware pipes 2′ long of the best quality	,,	45
3	21″ inside diameter cast iron manhole cover and frame for medium traffic.	,,	2
4	14″ x 10″ cast iron hinged lid and frame for cistern covers ...	,,	2
5	10″ cast iron square gratings	,,	2

List of articles required for providing sanitary fittings to Mr. Munivenkatappa's Wards at the Tuberculosis Sanatorium, Mysore.

	I. *Sanitary Fittings.*		
1	White Queensware lavatory basin of size 22″ x 16″, 3″ back skirting complete with nickle plated ½″ hot and cold taps, waste with rubber plug and brass chain painted cast iron brackets.	No.	1
2	Nickle plated brass towel rail 18″ long ½″ thick ...	,,	1
	II. *Waste and water connections.*		
3	2″ x 1½″ galvanized tee	No.	1
4	2″ galvanized pipe	R.ft.	28
5	2″ galvanized tee	No.	7
6	2″ galvanized collors	,,	1
7	2″ checknuts	,,	1
8	2″ wrought iron plugs	,,	6
9	1½″ x 1″ galvanized tee	,,	3
10	1½″ x ¾″ do	,,	1
11	1″ galvanized pipe	R.ft.	250
12	1″ elbow	No.	6
13	¾″ galvanized pipe	R.ft.	110
14	¾″ galvanized elbow	No.	30
15	¾″ x ½″ reducing collors	,,	7
16	¾″ clamps	,,	12
17	¾″ lead pipe	R.ft.	3
18	½″ do	,,	1½
19	1½″ galvanized pipe	,,	300
20	1½″ gunmetal gland cock heavy pattern	,,	1
21	¾″ screwdown stop cock with one side nickel plated union	No.	1
22	½″ screwdown bib cocks	,,	7
23	6″ x 6″ cast iron road box for gland cock cistern	,,	1

H. F. MARKER,
Executive Engineer.

6 c